

e-Permitting

miamidade.gov



FIRE DEPARTMENT PERMIT AND INSPECTION RECORD 12/17/2025  
 MUNICIPAL NO.2026-015965 FOLIO: 3220240110010  
 JOB SITE ADDRESS 14201 NW 60 AVE  
 PROPOSED USE WAREHOUSE/STORAGE  
 LEGAL 24 52 40 10.00 AC M/L MIAMI LAKES IND PARK SEC 3  
 APPLICATION TYPE ALTER INTERIOR 0 SQFT 0 UNITS 0 FLOORS  
 OWNER NAME CORDIS US CORP  
 CONTRACTOR AMERICAN FIRE SPRINKLER SERVICES LLC  
 QUALIFIER OWEIS OMAR  
 PERMIT TYPE FIRE  
 CATEGORIES 0032 FIRE SPRINKLERS

DATE: 12/17/2025 PROCESS NUMBER: M2026003985 NEW \*AMOUNT PAID 634.26  
 FIRE 13750 ALTERATIONS 145.82 FIRE 1 SPRINKLER UPF 187.00  
 FIRE 50 ROUGH INSP-FI 323.41 FIRE 50 FIRE SUPP TES 352.03  
 UBS1 1 BLDG 7.5% UPF 5.25 UPMU 70 UPFRONT FEE F 70.00

12/17/2025 15:11 BNZWEB1 182512176681 WEBIPAS 634.26

FIRE DEPARTMENT PERMIT AND INSPECTION RECORD 12/17/2025  
 MUNICIPAL NO.2026-015965 PROCESS NO. M2026003985 FOLIO: 3220240110010  
 JOB SITE ADDRESS 14201 NW 60 AVE  
 PROPOSED USE WAREHOUSE/STORAGE

REQUIRED INSPECTIONS INIT DATE  
 FIRE

0032 FIRE SPRINKLERS		
200 FIRE HYDRANTS	_____	_____
201 FIRE UNDERGROUND	_____	_____
202 FIRE PRESSURE TEST	_____	_____
206 FIRE ROUGH	_____	_____
207 FIRE PUMP PERFORMANCE TEST	_____	_____
210 FIRE STANDPIPE	_____	_____
215 FIRE FLUSH	_____	_____
209 FIRE FINAL	_____	_____

FIRE DEPARTMENT PERMIT AND INSPECTION RECORD 12/17/2025  
 MUNICIPAL NO.2026-015965 PROCESS NO. M2026003985 FOLIO: 3220240110010  
 JOB SITE ADDRESS 14201 NW 60 AVE  
 PROPOSED USE WAREHOUSE/STORAGE

TO SCHEDULE A FIRE INSPECTION, PLEASE VISIT THE WEB AT WWW.MIAMIDADE.GOV/BUILDING OR WWW.MIAMIDADE.GOV/FIRE. YOU WILL NEED TO PROVIDE YOUR TEN DIGIT MUNICIPAL INSPECTION NUMBER AND INSPECTION TYPE. THE INSPECTION TYPE CAN BE FOUND ON YOUR INSPECTION REQUIREMENTS AND RECORDS CARD.

IF YOU HAVE ANY QUESTIONS OR CONCERNS REGARDING AN INSPECTION, SCHEDULING A PRELIMINARY INSPECTION, OR LOAD BANK TEST INSPECTION, PLEASE CALL FIRE PREVENTION AT 786-331-4800.

IF YOU HAVE ANY QUESTIONS OR CONCERNS REGARDING A PLAN REVIEW, PLEASE CALL FIRE ENGINEERING AT (786) 315-2771.

\*\*BE ADVISED THIS IS NOT A PERMIT. PERMIT IS TO BE ISSUED BY YOUR CORRESPONDING MUNICIPAL BUILDING DEPARTMENT.

[Back to Main Menu](#)

---


[BLDG Home Page](#) | [BLDG Main Menu](#) | [BLDG Permit Menu](#) | [BLDG Plans Processing Menu](#) | [Inspection Types](#) | [Address Format](#)

[Home](#) | [About](#) | [Phone Directory](#) | [Privacy](#) | [Disclaimer](#)


E-mail your comments, questions and suggestions to [Webmaster](#)

This page was last edited on: February 23, 2004

Web Site © 2004 Miami-Dade County.  
All rights reserved.




**CORDIS**  
**MEZZANINE REMODELING**  
 14201 N.W. 60th AVENUE  
 MIAMI LAKES, FLORIDA 33014



**PROPOSED FLOOR PLAN - BUILDING 8C**  
 SCALE: 3/16" = 1'-0"




- GENERAL NOTES**
- NOTIFY THE ARCHITECT OF ANY UNEXPECTED FIELD CONDITION OR ANY DISCREPANCY BEFORE PROCEEDING. GENERAL CONTRACTOR TO COORDINATE COMPLETE SCOPE OF WORK WITH CONSTRUCTION DOCUMENTS.
  - REVIEW LAYOUT FOR CONSTRUCTION WITH OWNER IN FIELD PRIOR TO CONSTRUCTION.
  - PROVIDE STRICT CONTROL OF JOB CLEANING AND PREVENT DUST AND DEBRIS FROM EMANATING FROM CONSTRUCTION AREA.
  - ALL DEBRIS REMOVAL MUST BE PERFORMED IN ACCORDANCE WITH CORDIS REQUIREMENTS AND PROCEDURES. CONTRACTOR TO COORDINATE WITH CORDIS TO OBTAIN THE MOST RECENT REQUIREMENTS FOR DEBRIS REMOVAL.
  - DIMENSIONS ARE FROM FINISHED FACE OF WALL, U.O.N.
  - DRAWINGS ARE NOT TO BE SCALED. VERIFY ANY MISSING OR CONFLICTING WRITTEN DIMENSIONS WITH THE ARCHITECT / DESIGNER PRIOR TO CONSTRUCTION.
  - SYSTEM FURNITURE IS PROVIDED AND INSTALLED BY OWNER. CONTRACTOR TO CONNECT ELECTRICAL SERVICE.

- KEY NOTES**
- NEW CARPET TILE AND BASE, MATCH EXISTING
  - NEW PORCELAIN TILE FLOOR
  - RELOCATED TV.
  - 
  -




**DOOR SCHEDULE**

MARK	TYPE	MATERIAL	FRAME	WIDTH	HEIGHT	THICK.	LABEL	REMARKS
FIRST FLOOR								
101	I	HM	HM	3'-0"	7'-0"	1 3/4"	-	
102	I	HM	HM	3'-0"	7'-0"	1 3/4"	-	
103	II	GL/AL	AL	3'-0"	7'-0"	-	-	



**KEY PLAN**  
 SCALE: N.T.S.

This item has been digitally signed & sealed by Marcel R. Morlote, P.E. Printed copies of this document are not considered signed & sealed and the signature must be verified on any electronic copies.



WA PROJECT NO.: 22408.00  
 ISSUE DATE: 03/23/25

NO. REVISION DATE

**DRAWING TITLE**  
 PROPOSED FLOOR PLAN AND EQUIPMENT LAYOUT

**SHEET NUMBER**  
 A301



# Miami-Dade Department of Regulatory and Economic Resources CONTACT INFORMATION FOR PERMIT APPLICATION

FIRST NAME <i>(print clearly)</i> <b>MICHAEL</b>	LAST NAME <i>(print clearly)</i> <b>ANANIAN</b>
MOBILE PHONE <b>305-628-0100</b>	OFFICE/HOME PHONE <b>305-628-0100</b>
EMAIL <i>(required so you can be notified on the status of your plans)</i> <b>MIKE@AMERICANPERMITTING.COM and Permitting@mvfcg.com</b>	
COMMENTS <i>(If you are submitting a municipal plan, please provide the municipal process number(s) and ensure the municipal application is in the office set of plans.)</i>	

## PLANS *(check all that apply)*

**Please indicate if plans qualify for the following expedited plan reviews:**

<input type="checkbox"/> GOV'T PROJECT/DEPT _____	<input type="checkbox"/> GREEN BLDG* <i>(new construction only)</i>	<input type="checkbox"/> PACE PROJECT*
<input type="checkbox"/> AFFORDABLE/WORKFORCE HOUSING*	<input type="checkbox"/> ECONOMIC SIGNIFICANCE*	<input type="checkbox"/> CONCIERGE

*(\*Pursuant to Ordinance 99-140; Ordinance 05-115; and Ordinance 08-51. Project may have additional requirements.)*

**REQUESTED PLAN REVIEWS *(check all that apply for rework only)***

<input type="checkbox"/> ALL	<input type="checkbox"/> BLDG/HCAP	<input type="checkbox"/> ELEC	<input type="checkbox"/> ENRG	<input checked="" type="checkbox"/> FIRE	<input type="checkbox"/> ROOF
<input type="checkbox"/> LANDSCAPING	<input type="checkbox"/> MECH	<input type="checkbox"/> PLUM	<input type="checkbox"/> PWKS	<input type="checkbox"/> PWCC	<input type="checkbox"/> SIGN
<input type="checkbox"/> STRU	<input type="checkbox"/> ZNPR	<input type="checkbox"/> WASD	<input type="checkbox"/> PWIF	<input type="checkbox"/> LPGX	<input type="checkbox"/> SHOP DRAWING
<input type="checkbox"/> DERM CORE	<input type="checkbox"/> DERM AIR	<input type="checkbox"/> DERM AIRPORT	<input type="checkbox"/> DERM ASBESTOS	<input type="checkbox"/> DERM COASTAL	<input type="checkbox"/> DERM FLOOD
<input type="checkbox"/> DERM GREASE	<input type="checkbox"/> DERM INDUSTRIAL	<input type="checkbox"/> DERM PAVING & DRAINAGE	<input type="checkbox"/> DERM POLLUTION	<input type="checkbox"/> DERM PRE-TREATMENT	<input type="checkbox"/> DERM SOLID WASTE
<input type="checkbox"/> DERM TANKS	<input type="checkbox"/> DERM TREES	<input type="checkbox"/> DERM WATER TREATMENT	<input type="checkbox"/> DERM WETLANDS	<input type="checkbox"/> PERMIT BY AFFIDAVIT CHECK	<input type="checkbox"/> SHORT TERM EVENT AFFIDAVIT CHECK
<input type="checkbox"/> DOH/HRS					

**OPTIONAL PLAN REVIEWS *(check all that apply)***

<input type="checkbox"/> BLDG	<input type="checkbox"/> ELEC	<input type="checkbox"/> MECH	<input type="checkbox"/> PLUM	<input type="checkbox"/> STRU
-------------------------------	-------------------------------	-------------------------------	-------------------------------	-------------------------------

**OPR DERM INITIAL REVIEWS *(check all that apply)***

<input type="checkbox"/> DERM CORE	<input type="checkbox"/> DERM SPECIALTY <i>(You will be notified after core review is complete for additional fees)</i>
------------------------------------	-------------------------------------------------------------------------------------------------------------------------

**OPR DERM REWORK *(OPR for specialty only available at PIC)***

<input type="checkbox"/> TREE	<input type="checkbox"/> GREASE	<input type="checkbox"/> ASBESTOS	<input type="checkbox"/> COASTAL	<input type="checkbox"/> AIR	<input type="checkbox"/> PAVING & DRAINAGE
<input type="checkbox"/> TANKS	<input type="checkbox"/> INDUSTRIAL	<input type="checkbox"/> WETLAND	<input type="checkbox"/> PRE-TREATMENT	<input type="checkbox"/> CORE	<input type="checkbox"/> FLOOD

## FOR OFFICE USE ONLY

*To be completed by Permit and Occupancy Representative or Plans Processing Specialist*

APPLICATION DATE	CLERK NAME	ARRIVAL TIME
PROCESS NUMBER	PROCESS NUMBER	PROCESS NUMBER
<input type="checkbox"/> RE-ISSUE	<input type="checkbox"/> PLAN REVISION	<input type="checkbox"/> REWORK
<input type="checkbox"/> SHOP DRAWING		





## Installation Of Flexhead Commercial Sprinkler System

### 1. Mounting Bracket Assembly M#: MP-24-BKT-2

Remove one (1) 3/8" bolt and one (1) 1/4" bolt from hardware bag in box. Remove (1) universal hub and one (1) mounting bracket from box. Thread the 3/8" bolt through side of universal hub. Select one (1) of the four (4) sprinkler port locations on mounting bracket.

- Insert tab of universal hub into slot on mounting bracket as shown. **(Photo 1a)**
- Flip bracket over and insert and tighten 1/4" attachment bolt thru pre-punched hole in bracket until tight as shown. **(Photo 1b)**



1a



1b

### 2. Attach Mounting Bracket to T-bar Suspended Ceiling Grid.

**\*Note:** These products are designed for use with Intermediate or Heavy Duty ceiling grids manufactured to ASTM C 635 (*Standard Specification for the Manufacture, Performance, and Testing of Metal Suspension Systems for Acoustical Tile and Lay-in Panel Ceilings*) and ASTM C 636 (*Standard Practice for Installation of Metal Ceiling Suspension Systems for Acoustical Tile and Lay-in Panels*) Designation.


A. From above the ceiling, position FlexHead Mounting Bracket ends on to T-bar grid so that the center hole in support bracket aligns directly above the sprinkler hole prepared in ceiling tile. Be sure the center section of the bracket end is on the outside of grid and base section is on the inside. Position the ends of the support bracket on the T-bar grid and push each of the two (2) ends of the bracket down to snap in place as shown. **(Photo 2)**



2

### 3. Anchor Bracket to T-bar Grid

A. Anchor bracket to t-bar grid with self tapping screw through bottom hole in bracket end into grid. Be sure to install self tapping screw in lower hole of bracket end with attachment clip as shown. Repeat process on opposite end of bracket. Both ends of bracket should be anchored as shown. **(Photo 3)**



3

### 4. Connect FlexHead to Sprinkler Branch-line

Apply teflon tape and pipe sealant to one inch (1") threaded end of FlexHead Sprinkler Drop per NFPA guidelines. Attach one inch (1") threaded end of FlexHead Sprinkler Drop to branch-line per NFPA, State and local code guidelines.

The flexible hose with fitting is only intended to be installed with bends.

Do not use welded or braided hose section of FlexHead Sprinkler Drop for a wrenching surface.

**Attach FlexHead Sprinkler Drop using rigid pipe end of units as wrenching surface as shown. (Photo 4)**



4

### 5. Secure FlexHead Sprinkler Drop to Mounting Bracket and install Sprinkler Head.

A. Bend the Flexhead to hold its desired position. **Do not overbend the flexible hose. FlexHead has a 3" (75mm) minimum bend radius.** Insert reducing coupling end of FlexHead Sprinkler Drop through center hole in previously installed support bracket and hole in ceiling tile. Make sure the hose is bent sufficiently so that the reducing coupling sits perfectly vertical in center hole of support bracket. Do not torque or twist FlexHead during installation process. **(Photo 5a)**



5a

B. Attach sprinkler head, properly prepared with teflon tape and sealant to FlexHead Sprinkler Drop according to NFPA and sprinkler head manufacturer's guidelines. **(Photo 5b)**



5b

C. Adjust FlexHead Sprinkler height to accommodate type of sprinkler head. When sprinkler head is in desired location, tighten the fastening bolt on center hub of support bracket by turning clockwise hand tight plus 1 turn (100 inch lbs) with wrench as shown. After tightening the bolt, tighten the nut hand tight plus 1 turn (100 inch lbs) with wrench. **(Photo 5c)**



5c

### 6. Installation of the FlexHead Ceiling Sprinkler System is complete.

\*Test installation of sprinkler system for any leaks per NFPA Guidelines.

\*Install sprinkler escutcheon from below ceiling per manufacturers guidelines.

Flexhead Industries, Inc.  
56 Lowland Street  
Holliston, MA 01746

Tel 800-829-6975 / 508-893-9596  
Fax 508-893-6020 / www.flexhead.com

U.S and International Patent Pending: #6,123,154, #6,119,784, #6,752,218, #7,032,680, #6,488,097

FGG/BM System Compatible indicates this product has been tested and is monitored on an ongoing basis to assure chemical compatibility with

Fire and Life Safety Department of Regulatory and Economic Resources Job Copy  
3226003985 12/17/2025 3:12:04 PM

Flex Heads - Spec Sheets.pdf


Examiner Date Time Stamp Trade Stamp Name  
CARRIER, KEVIN 12/9/2025 8:26:24 PM FIRE Reference Only.


# FlexHead Friction Loss Data

Flexhead Model #	Outlet Size  in (cm)	Hose Assembly Length  Ft (m)	Maximum Number of 90-Degree Bends (3 in. Bending Radius)	Maximum Equivalent Length of Schedule 40, Nominal 1 in Diameter Pipe (C=120), ft	Maximum Ambient Temperature Rating F (C)	Maximum Rated Pressure		Maximum K-factor & Orifice of Sprinkler K-factor/ orifice
						psi (kPa)	H-Series psi (kPa)	
2024, 2024H	1/2 (1.27)	2 (0.6)	3	11	300° (148°)	175 (1205) / 300 (2068)		5.62 / 1/2"
2036, 2036H	1/2 (1.27)	3 (0.9)	3	16	300° (148°)	175 (1205) / 300 (2068)		5.62 / 1/2"
2048, 2048H	1/2 (1.27)	4 (1.2)	4	24	300° (148°)	175 (1205) / 300 (2068)		5.62 / 1/2"
2060, 2060H	1/2 (1.27)	5 (1.5)	4	29	300° (148°)	175 (1205) / 300 (2068)		5.62 / 1/2"
2072, 2072H	1/2 (1.27)	6 (1.8)	4	35	300° (148°)	175 (1205) / 300 (2068)		5.62 / 1/2"
2024E, 2024HE	3/4 (1.90)	2 (0.6)	3	12	300° (148°)	175 (1205) / 300 (2068)		14.0 / 3/4"
2036E, 2036HE	3/4 (1.90)	3 (0.9)	3	18	300° (148°)	175 (1205) / 300 (2068)		14.0 / 3/4"
2048E, 2048HE	3/4 (1.90)	4 (1.2)	4	23	300° (148°)	175 (1205) / 300 (2068)		14.0 / 3/4"
2060E, 2060HE	3/4 (1.90)	5 (1.5)	4	29	300° (148°)	175 (1205) / 300 (2068)		14.0 / 3/4"
2072E, 2072HE	3/4 (1.90)	6 (1.8)	4	32	300° (148°)	175 (1205) / 300 (2068)		14.0 / 3/4"
2024E, 2024HE	3/4 (1.90)	2 (0.6)	3	18	300° (148°)	175 (1205) / 300 (2068)		14.0 / 3/4"
2036E, 2036HE	3/4 (1.90)	3 (0.9)	3	23	300° (148°)	175 (1205) / 300 (2068)		14.0 / 3/4"
2048E, 2048HE	3/4 (1.90)	4 (1.2)	4	23	300° (148°)	175 (1205) / 300 (2068)		14.0 / 3/4"
2060E, 2060HE	3/4 (1.90)	5 (1.5)	4	29	300° (148°)	175 (1205) / 300 (2068)		14.0 / 3/4"
2072E, 2072HE	3/4 (1.90)	6 (1.5)	4	32	300° (148°)	175 (1205) / 300 (2068)		14.0 / 3/4"

F R I C T I O N L O S S

- FlexHead products are intended for use in hydraulically designed wet, pre-action, deluge or dry pipe sprinkler per NFPA 13, 13R, and 13D guidelines.
- The hydraulic loss of FlexHead should be included in the hydraulic design calculations the same as a valve or fitting.
- Each FlexHead Sprinkler Drop has a 3" minimum bend radius per UL guidelines. FlexHead products are listed to limited flexibility standards and are intended for direct connection to fire sprinklers.
- Bracket System MP-24-BKT-2 has a minimum of 6 inch and a maximum of 24 inch spacing requirement for anchoring to the building component.





AMERICAN FIRE SPRINKLER SERVICES, LLC.  
 3371 N.W. 154th TERRACE  
 MIAMI GARDENS, FLORIDA 33054  
 PHONE: 305-628-0100 FAX: 305-628-3556


COMPANY NAME:  
 SDA CONSTRUCTION CORP  
 JAYR LUDKA  
 305-771-6847  
 PHONE NO.  
 FIELD CONTACT  
 SAME  
 PHONE NO.  
 ESTIMATE NO. E79447  
 ADDITIONAL INFO.

PROJECT NAME:  
 CORDIS - MEZZANINE OFFICE  
 14201 NW 60TH AVENUE  
 MIAMI FL, 33014

Digitally signed by  
 Robert Weinstein  
 Date: 2025.05.21  
 15:43:03 -04'00'

DATE PRINTED: 5/16/25  
 DATE: 5/16/25  
 DESIGNED BY: A.M.  
 DRAWN BY: A.M.  
 CHECKED BY: R.W.  
 MARK: R.W.  
 SCALE: AS NOTED  
 SHEET: FP-1 OF 1

FP-1 OF 1




FIRE SPRINKLER SYSTEM OFFICE MEZZANINE PLAN  
 SCALE: 3/16" = 1'-0"

Scope of work:  
 Existing fully protected building supplied by a fire pump. Relocate and add fire sprinkler heads as shown on plans as needed to obtain proper coverage due to renovations. TOTAL SQFT: 8975.00


Symbol	Count	Thread	K-Factor	Description	Note	Coverage
●	48	1/2"	5.6	TY3531: (RF-II) QUICK RESPONSE WHITE CONCEALED PENDNET 155° DEGREES	NEW	PER NFPA
✕				EXISTING CHROME RECESSED PENDNET TO BE PLUGGED	EXISTING TO BE PLUGGED/ REMOVED	
▲	2	1/2"	5.6	TY3332: (TY-FRB) QUICK RESPONSE WHITE RECESSED SIDEWALL 200° DEGREES	NEW	PER NFPA

50 = Total Number of Heads On Job





FIRE APPROVED PAGE  
 CARRIER, KEVIN, 12/9/2025 8:20:47 PM

NFPA 13 - 2019 Edition  
 28.2 Acceptance Requirements.  
 28.2.1 Hydrostatic Tests.  
 28.2.1.1 Unless permitted by 28.2.1.3 through 28.2.1.5, all piping and attached appurtenances subjected to system working pressure shall be hydrostatically tested at 200 psi (14 bar) and shall maintain that pressure without loss for 2 hours.  
 28.2.1.2 Loss shall be determined by a drop in gauge pressure or visual leakage.  
 28.2.1.3 Portions of systems normally subjected to system working pressures in excess of 150 psi (10 bar) shall be tested as described in 28.2.1.1, at a pressure of 50 psi (3.4 bar) in excess of system working pressure.  
 28.2.1.4 Where cold weather will not permit testing with water, an interim air test shall be permitted to be conducted as described in 28.2.2. This provision shall not remove or replace the requirement for conducting the hydrostatic test as described in 28.2.1.1.  
 28.2.1.5 The test pressure shall be read from a gauge located at the low elevation point of the system or portion being tested. The pressures in piping at higher elevations shall be permitted to be less than 200 psi (14 bar) when accounting for elevation losses. Systems or portions of systems that can be isolated shall be permitted to be tested separately.  
 28.2.1.6 Additives, corrosive chemicals such as sodium silicate, or derivatives of sodium silicate, brine, or similar acting chemicals shall not be used while hydrostatically testing systems or for stopping leaks.  
 28.2.1.7 Piping between the exterior fire department connection and the check valve in the fire department inlet pipe shall be hydrostatically tested in the same manner as the balance of the system. After repair or replacement work affecting the fire department connection, the piping between the exterior and the check valve in the fire department inlet pipe shall be isolated and hydrostatically tested at 150 psi (10 bar).  
 28.2.1.8 When systems are being hydrostatically tested, tests shall be permitted to be conducted with pendent or horizontal sidewall sprinklers or plugs installed in fittings. Any plugs shall be replaced with pendent or horizontal sidewall sprinklers after the test is completed.  
 28.2.1.9 When deluge systems are being hydrostatically tested, plugs shall be installed in fittings and replaced with open sprinklers after the test is completed, and the operating elements of automatic sprinklers shall be removed after the test is completed.  
 28.2.1.10 Provision shall be made for the proper disposal of water used for flushing or testing.




- General Notes
- All piping, heads, hangers, and system components to be spaced and installed in accordance with the approving authority having jurisdiction. All applicable state & local codes, and the latest adopted NFPA standards. (NFPA 13, 2019 Ed.)
  - Aboveground piping 1"-2" to be threaded and/or grooved with screwed or grooved fittings (or approved acceptable equal).
  - Piping to be supported from structural members as shown on plans.
  - Armover piping exceeding 24" in length shall receive a hanger.
  - Fire sprinkler heads to be spaced at 130 sqft per head for ordinary hazard areas (Seating, Restrooms, & Office).
  - Sprinkler heads in areas exposed to corrosive elements shall have a corrosive resistant.
  - Verify all conditions & coordinate with other trades prior to installation.
  - Sprinkler heads to be positioned with regard to all obstructions (Hvac Ductwork, Lighting, Speakers, Structural Members, etc.)




	1	1 1/4	1 1/2	2	2 1/2	3	4	6	8
1	12	12	12	12	12	12	N/A	N/A	N/A
2	12	12	15	15	15	15	15	15	15

ALL HANGERS AT CEILING PENDENT END OF LINE SPRINKLERS SHALL PREVENT UPWARD MOVEMENT OF PIPE. HANGERS AT ARMOVERS TO CEILING PENDENT



PIPING SUPPORT DETAILS





**AMERICAN FIRE SPRINKLER  
SERVICES**


American Fire Sprinkler Serv.  
3371 NW 154th Terrace  
Miami Gardens FL, 33054  
305-628-0100



This item has been electronically signed and sealed by Robert Weinstein, P.E. using a Digital Signature and date. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Digitally signed by  
Robert Weinstein  
Date: 2025.05.21  
15:43:59 -04'00'

Job Name : Cordis (Office Reovation) Area #1  
Drawing : FP-1  
Location : 14201 Northwest 60th Avenue Miami Lakes FL, 33014  
Remote Area : 1  
Contract : E79447  
Data File : Cordis HydraCalcs Office.WXF



**HYDRAULIC CALCULATIONS**  
*for*

**Project name:** Cordis (Office Reovation) Area #1  
**Location:** 14201 Northwest 60th Avenue Miami Lakes FL, 33014  
**Drawing no:** FP-1  
**Date:** 5/9/25

**Design**

**Remote area number:** 1  
**Remote area location:** Office Area  
**Occupancy classification:** Light Hazard  
**Density:** .10 - Gpm/SqFt  
**Area of application:** 1112.00 - SqFt  
**Coverage per sprinkler:** 196 - SqFt  
**Type of sprinklers calculated:** Tyco TY3531  
**No. of sprinklers calculated:** 10  
**In-rack demand:** - GPM  
**Hose streams:** 100 - GPM  
**Total water required (including hose streams):** 307.818 - GPM @ 30.758 - Psi  
**Type of system:** Wet System  
**Volume of dry or preaction system:** - Gal

**Water supply information**

**Date:** 08/27/24  
**Location:** 14201 Northwest 60th Avenue Miami Lakes FL, 33014  
**Source:** Cintas Fire Protection Annual Fire Pump Report


**Name of contractor:** American Fire Sprinkler Serv.  
**Address:** 3371 NW 154th Terrace / / Miami Gardens FL, 33054  
**Phone number:** 305-628-0100  
**Name of designer:** Armani Mesa  
**Authority having jurisdiction:** City of Miami Dade Fire Division  
**Notes: (Include peaking information or gridded systems here.)**

# Water Supply Curve C

Miami-Dade County Department of Regulatory and Economic Resources  
 322609385 - 12/17/2025 3:12:04 PM  
 American Fire Sprinkler Serv.  
 Ordis (Office Reovation) Area #1

**Demand:**  
 D1 - Elevation : 2.599  
 D2 - System Flow : 207.818  
 D2 - System Pressure : 30.758  
 Hose ( Demand ) : 100  
 D3 - System Demand : 307.818  
 Safety Margin : 81.082

**City Water Supply:**  
 C1 - Static Pressure : 112  
 C2 - Residual Pressure: 109  
 C2 - Residual Flow : 1500



**Fittings Used Summary**

Miami-Dade County Department of Regulatory and Economic Resources  
 32260933085  
 12/19/2025 3:12:04 PM  
 HYDRAULIC CALC.pdf

Fitting Legend Abbrev. Name	1/2	3/4	1	1 1/4	1 1/2	2	2 1/2	3	3 1/2	4	5	6	8	10	12	14	16	18	20	24
NFPA 13 Butterfly Valve	0	0	0	0	0	6	7	10	0	12	9	10	12	19	21	0	0	0	0	0
NFPA 13 90° Standard Elbow	1	2	2	3	4	5	6	7	8	10	12	14	18	22	27	35	40	45	50	61
Flow Switch Potter VSR																				
NFPA 13 90° Flow thru Tee	3	4	5	6	8	10	12	15	17	20	25	30	35	50	60	71	81	91	101	121

Fitting generates a Fixed Loss Based on Flow

**Units Summary**

Diameter Units Inches  
 Length Units Feet  
 Flow Units US Gallons per Minute  
 Pressure Units Pounds per Square Inch

Note: Fitting Legend provides equivalent pipe lengths for fittings types of various diameters. Equivalent lengths shown are standard for actual diameters of Sched 40 pipe and CFactors on 120 except as noted with \*. The fittings marked with a \* show equivalent lengths values supplied by manufacturers based on specific pipe diameters and CFactors and they require no adjustment. All values for fittings not marked with a \* will be adjusted in the calculation for CFactors of other than 120 and diameters other than Sched 40 per NFPA.

# Flow Summary - NFPA

American Fire Sprinkler Serv.  
Cordis (Office Reovation) Area #1

Page 4  
Date 5/9/25

## SUPPLY ANALYSIS

<i>Node at Source</i>	<i>Static Pressure</i>	<i>Residual Pressure</i>	<i>Flow</i>	<i>Available Pressure</i>	<i>Total Demand</i>	<i>Required Pressure</i>
FP	112.0	109	1500.0	111.84	307.82	30.758

## NODE ANALYSIS

<i>Node Tag</i>	<i>Elevation</i>	<i>Node Type</i>	<i>Pressure at Node</i>	<i>Discharge at Node</i>	<i>Notes</i>
201	9.0	5.6	12.25	19.6	
202	9.0	5.6	12.46	19.77	
203	9.0	5.6	12.94	20.14	
204	9.0	5.6	12.85	20.08	
205	9.0	5.6	13.75	20.77	
206	9.0	5.6	13.99	20.95	
207	9.0	5.6	14.74	21.5	
208	9.0	5.6	14.49	21.32	
209	9.0	5.6	14.74	21.5	
210	9.0	5.6	15.72	22.2	
101	13.0		13.78		
102	13.0		14.04		
103	13.0		14.63		
104	13.0		14.53		
105	13.0		15.64		
106	13.0		15.94		
107	13.0		16.87		
108	13.0		16.56		
109	13.0		16.87		
110	13.0		18.09		
P1	13.0		14.53		
P2	13.0		14.81		
P3	13.0		15.9		
P4	13.0		16.48		
P5	13.0		16.79		
P6	13.0		18.0		
P7	13.0		17.44		
P8	13.0		17.77		
P9	13.0		19.04		
3A	13.0		19.85		
2A	13.0		20.58		
1A	13.0		21.75		
3	12.0		20.96		
2	12.0		21.46		
1	12.0		22.65		
T	12.0		25.05		
TOR	12.0		25.46		
BOR	3.0		30.45	50.0	
E1	3.0		30.49		
E2	-3.0		33.11		
E3	-3.0		33.12		
E4	-3.0		33.31		

# Flow Summary - NFPA

American Fire Sprinkler Serv.  
Cordis (Office Reovation) Area #1

Page 5  
Date 5/9/25

---

## NODE ANALYSIS (cont.)

<i>Node Tag</i>	<i>Elevation</i>	<i>Node Type</i>	<i>Pressure at Node</i>	<i>Discharge at Node</i>	<i>Notes</i>
E5	3.0		30.72		
FP	3.0		30.76	50.0	

# Final Calculations : Hazen-Williams

American Fire Sprinkler Serv.  
Cordis (Office Reovation) Area #1

Page 6  
Date 5/9/25

Node1 to Node2	Elev1 Elev2	K Fact	Qa Qt	Nom Act	Fitting or Eqiv	Len	Pipe Ftngs Total	CFact Pf/Ft	Pt Pe Pf	*****	Notes	*****
201 to 101	9 13	5.60	19.60 19.6	1 1.049	E	2.0 0.0 0.0	24.000 2.000 26.000	120 0.1253	12.250 -1.732 3.259		Vel = 7.28	
101			0.0 19.60						13.777		K Factor = 5.28	
202 to 102	9 13	5.60	19.77 19.77	1 1.049	E	2.0 0.0 0.0	24.000 2.000 26.000	120 0.1274	12.465 -1.732 3.312		Vel = 7.34	
102			0.0 19.77						14.045		K Factor = 5.28	
203 to 103	9 13	5.60	20.14 20.14	1 1.049	E	2.0 0.0 0.0	24.000 2.000 26.000	120 0.1318	12.937 -1.732 3.428		Vel = 7.48	
103			0.0 20.14						14.633		K Factor = 5.26	
204 to 104	9 13	5.60	20.08 20.08	1 1.049	E	2.0 0.0 0.0	24.000 2.000 26.000	120 0.1311	12.854 -1.732 3.408		Vel = 7.45	
104			0.0 20.08						14.530		K Factor = 5.27	
205 to 105	9 13	5.60	20.77 20.77	1 1.049	E	2.0 0.0 0.0	24.000 2.000 26.000	120 0.1395	13.750 -1.732 3.626		Vel = 7.71	
105			0.0 20.77						15.644		K Factor = 5.25	
206 to 106	9 13	5.60	20.95 20.95	1 1.049	E	2.0 0.0 0.0	24.000 2.000 26.000	120 0.1417	13.990 -1.732 3.685		Vel = 7.78	
106			0.0 20.95						15.943		K Factor = 5.25	
207 to 107	9 13	5.60	21.50 21.5	1 1.049	E	2.0 0.0 0.0	24.000 2.000 26.000	120 0.1488	14.739 -1.732 3.868		Vel = 7.98	
107			0.0 21.50						16.875		K Factor = 5.23	
208 to 108	9 13	5.60	21.32 21.32	1 1.049	E	2.0 0.0 0.0	24.000 2.000 26.000	120 0.1464	14.488 -1.732 3.806		Vel = 7.91	
108			0.0 21.32						16.562		K Factor = 5.24	
209 to 109	9 13	5.60	21.50 21.5	1 1.049	E	2.0 0.0 0.0	24.000 2.000 26.000	120 0.1487	14.740 -1.732 3.867		Vel = 7.98	
109			0.0 21.50						16.875		K Factor = 5.23	
210 to 110	9 13	5.60	22.20 22.2	1 1.049	E	2.0 0.0 0.0	24.000 2.000 26.000	120 0.1578	15.717 -1.732 4.104		Vel = 8.24	

# Final Calculations : Hazen-Williams

American Fire Sprinkler Serv.  
Cordis (Office Reovation) Area #1

Page 7  
Date 5/9/25

Node1 to Node2	Elev1 Elev2	K Fact	Qa Qt	Nom Act	Fitting or Eqiv	Len	Pipe Ftngs Total	CFact Pf/Ft	Pt Pe Pf	*****	Notes	*****
			0.0 22.20						18.089		K Factor = 5.22	
101 to P1	13 13		19.60 19.6	1 1.049	T	5.0 0.0	1.000 5.000	120 0.1253	13.777 0.0 0.752		Vel = 7.28	
P1			0.0 19.60						14.529		K Factor = 5.14	
102 to P2	13 13		19.77 19.77	1 1.049	T	5.0 0.0	1.000 5.000	120 0.1273	14.045 0.0 0.764		Vel = 7.34	
P2			0.0 19.77						14.809		K Factor = 5.14	
103 to P3	13 13		20.14 20.14	1 1.049	T	5.0 0.0	4.580 5.000	120 0.1318	14.633 0.0 1.263		Vel = 7.48	
P3			0.0 20.14						15.896		K Factor = 5.05	
104 to P3	13 13		20.08 20.08	1 1.049	T	5.0 0.0	5.420 5.000	120 0.1311	14.530 0.0 1.366		Vel = 7.45	
P3			0.0 20.08						15.896		K Factor = 5.04	
105 to P4	13 13		20.77 20.77	1 1.049	T	5.0 0.0	1.000 5.000	120 0.1397	15.644 0.0 0.838		Vel = 7.71	
P4			0.0 20.77						16.482		K Factor = 5.12	
106 to P5	13 13		20.95 20.95	1 1.049	T	5.0 0.0	1.000 5.000	120 0.1417	15.943 0.0 0.850		Vel = 7.78	
P5			0.0 20.95						16.793		K Factor = 5.11	
107 to P6	13 13		21.50 21.5	1 1.049	T	5.0 0.0	2.580 5.000	120 0.1487	16.875 0.0 1.127		Vel = 7.98	
P6			0.0 21.50						18.002		K Factor = 5.07	
108 to P7	13 13		21.32 21.32	1 1.049	T	5.0 0.0	1.000 5.000	120 0.1463	16.562 0.0 0.878		Vel = 7.91	
P7			0.0 21.32						17.440		K Factor = 5.11	
109 to P8	13 13		21.50 21.5	1 1.049	T	5.0 0.0	1.000 5.000	120 0.1488	16.875 0.0 0.893		Vel = 7.98	
P8			0.0 21.50						17.768		K Factor = 5.10	

# Final Calculations : Hazen-Williams

American Fire Sprinkler Serv.  
Cordis (Office Reovation) Area #1

Page 8  
Date 5/9/25

Node1 to Node2	Elev1 Elev2	K Fact	Qa Qt	Nom Act	Fitting or Eqiv	Len	Pipe Ftngs Total	CFact Pf/Ft	Pt Pe Pf	*****	Notes	*****
110 to P9	13 13		22.20 22.2	1 1.049	T	5.0 0.0	1.000 5.000 6.000	120 0.1578	18.089 0.0 0.947		Vel = 8.24	
P9			0.0 22.20						19.036		K Factor = 5.09	
P1 to P2	13 13		19.60 19.6	1.5 1.61	T	8.0 0.0	10.000 8.000 18.000	120 0.0156	14.529 0.0 0.280		Vel = 3.09	
P2 to P3	13 13		19.77 39.37	1.5 1.61	T	8.0 0.0	11.210 8.000 19.210	120 0.0566	14.809 0.0 1.087		Vel = 6.20	
P3 to 3A	13 13		40.22 79.59	1.5 1.61	E	4.0 0.0	15.000 4.000 19.000	120 0.2079	15.896 0.0 3.951		Vel = 12.54	
3A			0.0 79.59						19.847		K Factor = 17.87	
P4 to P5	13 13		20.77 20.77	1.5 1.61	T	8.0 0.0	10.000 8.000 18.000	120 0.0173	16.482 0.0 0.311		Vel = 3.27	
P5 to P6	13 13		20.94 41.71	1.5 1.61	T	8.0 0.0	11.210 8.000 19.210	120 0.0629	16.793 0.0 1.209		Vel = 6.57	
P6 to 2A	13 13		21.50 63.21	1.5 1.61	E	4.0 0.0	15.000 4.000 19.000	120 0.1358	18.002 0.0 2.580		Vel = 9.96	
2A			0.0 63.21						20.582		K Factor = 13.93	
P7 to P8	13 13		21.32 21.32	1.5 1.61	T	8.0 0.0	10.000 8.000 18.000	120 0.0182	17.440 0.0 0.328		Vel = 3.36	
P8 to P9	13 13		21.49 42.81	1.5 1.61	T	8.0 0.0	11.210 8.000 19.210	120 0.0660	17.768 0.0 1.268		Vel = 6.75	
P9 to 1A	13 13		22.21 65.02	1.5 1.61	E	4.0 0.0	15.000 4.000 19.000	120 0.1431	19.036 0.0 2.718		Vel = 10.25	
1A			0.0 65.02						21.754		K Factor = 13.94	
3A to 3	13 12		79.59 79.59	2 2.067	T	10.0 0.0	1.000 10.000 11.000	120 0.0616	19.847 0.433 0.678		Vel = 7.61	
3			0.0 79.59						20.958		K Factor = 17.39	
2A to 2	13 12		63.21 63.21	2 2.067	T	10.0 0.0	1.000 10.000 11.000	120 0.0403	20.582 0.433 0.443		Vel = 6.04	
			0.0									

# Final Calculations : Hazen-Williams

American Fire Sprinkler Serv.  
Cordis (Office Reovation) Area #1

Page 9  
Date 5/9/25

Node1 to Node2	Elev1 Elev2	K Fact	Qa Qt	Nom Act	Fitting or Eqiv	Len	Pipe Ftngs Total	CFact Pf/Ft	Pt Pe Pf	*****	Notes	*****
			63.21						21.458		K Factor = 13.65	
1A to 1	13 12		65.02	2	T	10.0	1.000	120	21.754			
						0.0	10.000		0.433			
			65.02	2.067		0.0	11.000	0.0424	0.466		Vel = 6.22	
			0.0									
1			65.02						22.653		K Factor = 13.66	
3 to 2	12 12		79.59	2.5	T	16.474	10.000	120	20.958			
						0.0	16.474		0.0			
			79.59	2.635		0.0	26.474	0.0189	0.500		Vel = 4.68	
2 to 1	12 12		63.21	2.5	T	16.474	5.000	120	21.458			
						0.0	16.474		0.0			
			142.8	2.635		0.0	21.474	0.0556	1.195		Vel = 8.40	
1 to T	12 12		65.02	2.5	T	16.474	5.000	120	22.653			
						0.0	16.474		0.0			
			207.82	2.635		0.0	21.474	0.1115	2.394		Vel = 12.23	
T to TOR	12 12		0.0	6	3E	52.808	218.000	120	25.047			
						0.0	52.808		0.0			
			207.82	6.357		0.0	270.808	0.0015	0.414		Vel = 2.10	
			0.0									
TOR			207.82						25.461		K Factor = 41.19	
TOR to BOR	12 3		207.82	6	T Fsp B	37.72	9.000	120	25.461			
						0.0	50.293		4.898		** Fixed Loss = 1	
			207.82	6.357		12.573	59.293	0.0015	0.091		Vel = 2.10	
BOR to E1	3 3	H50	50.00	8	T E	41.108	3.420	120	30.450			
						21.141	62.249		0.0			
			257.82	8.249		0.0	65.669	0.0006	0.042		Vel = 1.55	
			0.0									
E1			257.82						30.492		K Factor = 46.69	
E1 to E2	3 -3		257.82	8	E	21.141	5.000	120	30.492			
						0.0	21.141		2.599			
			257.82	8.249		0.0	26.141	0.0006	0.016		Vel = 1.55	
E2 to E3	-3 -3		0.0	8	E	21.141	6.000	120	33.107			
						0.0	21.141		0.0			
			257.82	8.249		0.0	27.141	0.0007	0.018		Vel = 1.55	
E3 to E4	-3 -3		0.0	8	2E	56.936	325.000	140	33.125			
						0.0	56.936		0.0			
			257.82	8.27		0.0	381.936	0.0005	0.181		Vel = 1.54	
E4 to E5	-3 3		0.0	8	E	28.468	6.000	140	33.306			
						0.0	28.468		-2.599			
			257.82	8.27		0.0	34.468	0.0005	0.017		Vel = 1.54	
E5 to FP	3 3		0.0	8	2E	42.282	10.000	120	30.724			
						0.0	42.282		0.0			
			257.82	8.249		0.0	52.282	0.0007	0.034		Vel = 1.55	
			50.00								Qa = 50.00	
FP			307.82						30.758		K Factor = 55.50	

**MIAMI-DADE COUNTY**

**DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES**

<http://www.miamidade.gov/building/home.asp>

12/17/2025 3:12:04 PM

<b>Tracking #</b>	<b>Process #</b>	<b>Permit #</b>
3226003985	M2026003985	2026015965

<b>THIS COPY OF PLANS MUST BE AVAILABLE ON BUILDING SITE OR AN INSPECTION WILL NOT BE MADE.</b>				
<b>Process #</b>	<b>Review</b>	<b>Disposition</b>	<b>Reviewer</b>	<b>Date</b>
M2026003985	FIRE	A	CARRIER, KEVIN	12/9/2025
M2026003985	UPFRONT FEES	A	WEB APPLICATION ID	11/25/2025

**Disclaimer.**

Subject to compliance with all Federal, State, and County Laws, rules and regulations. Miami-Dade County assumes no responsibility for accuracy of or results of these plans.

**NOTICE:** In addition to the requirements of this permit, there may be additional restrictions applicable to the property that may be found in the public records of this county, and there may be additional permits required from other governmental entities such as water management districts, state agencies or federal agencies.

<b>Stamp Name</b>	<b>Trade</b>	<b>Disposition</b>	<b>Stamp Description</b>
Approved	FIRE	A	Approved
Reference Only.	FIRE	R	Reference only.

Permitting @ M/V/FCG.com

## NOTE: ALL SHEETS MUST BE REVIEWED

MIAMI-DADE COUNTY DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES

Herbert S. Saffir Permitting and Inspection Center

11805 SW 26th Street (Coral Way) • Miami, Florida 33175-2474 • (786) 315-2000

### APPLICATION FOR MUNICIPAL PERMIT APPLICANTS

**THAT REQUIRE PLAN REVIEW FROM MIAMI-DADE FIRE RESCUE**

**AND/OR ENVIRONMENTAL SERVICES**

M2026003985      SME2025-3195      3226003985

**PROVIDE MUNICIPAL PROCESS NUMBER HERE**

<b>LOCATION OF IMPROVEMENTS</b>	Job Address <u>14201 NW 60TH AVENUE, MIAMI LAKES, FL 33014</u> Folio <u>32-2024-011-0010</u> Lot _____ Block _____ Subdivision <u>N/A</u> PBpg _____ Metes and bounds _____	<b>CONTRACTOR INFORMATION</b>	Contractor No. <u>FPC17-000109</u> Last four (4) digits of Qualifier No. <u>9545</u> Contractor Name <u>American Fire Sprinkler Services, LLC.</u> Qualifier Name <u>OMAR OWEIS</u> Address <u>3371 NW 154th Terrace</u> City <u>Miami Gardens</u> State <u>FL</u> Zip <u>33054</u>
<b>TYPE OF IMPROVEMENTS</b>	<input type="checkbox"/> New Construction on Vacant Land <input checked="" type="checkbox"/> Alteration Interior <input type="checkbox"/> Alteration Exterior <input type="checkbox"/> Relocation of Structure <input type="checkbox"/> Enclosure <input type="checkbox"/> Repair <input type="checkbox"/> Repair Due to Fire	<input type="checkbox"/> Demolish <input type="checkbox"/> Shell Only <input type="checkbox"/> Addition Attached <input type="checkbox"/> Addition Detached <input type="checkbox"/> Re-Roof <input type="checkbox"/> Foundation Only <input type="checkbox"/> Tent	Current use of property <u>CONDOMINIUM: COMMERCIAL</u> Description of Work <u>ADD/RELOCATE (48) FIRE SPRINKLER HEADS</u> Sq. Ft. _____ Units _____ Floors _____ Value of Work <u>\$ 13,750</u>
<b>PERMIT TYPE</b>	<input type="checkbox"/> MBLD* Category _____ <input type="checkbox"/> MELE _____ <input type="checkbox"/> MPLU _____ <input type="checkbox"/> MLPG _____ <input type="checkbox"/> MMEC _____ <input checked="" type="checkbox"/> FIRE <u>32</u>	<b>REVIEW STATUS</b>	<input type="checkbox"/> Chg. Contractor <input type="checkbox"/> Re-Issue <input type="checkbox"/> Re-Stamp <input type="checkbox"/> Revision <input type="checkbox"/> Not Applicable for Fire
<b>PERSON TO PICK UP PLANS</b>	Name <u>MICHAEL ANANIAN</u> Address <u>3371 NW 154th Terrace</u> City <u>Miami Gardens</u> State <u>FL</u> Zip <u>33054</u> Phone <u>(305) 525-1449</u>	<b>ARCHITECT / ENGINEER</b>	Owner _____ Address _____ City _____ State _____ Zip _____ Phone _____
<b>FIRE SPECIAL REQUEST PLAN REVIEW (SRI)</b>	I am requesting a Special Request Plan Review (SRI) to be scheduled as soon as possible. There is a minimum charge of one-hour. Please contact the Fire Department for current rate.		
	1 <sup>st</sup> Request: _____ Date: _____ 2 <sup>nd</sup> Request: _____ Date: _____ 3 <sup>rd</sup> Request: _____ Date: _____		
<p><b>If the applicant is a known named violator with: unpaid civil penalties; unpaid administrative costs of hearing; unpaid County investigative, enforcement, testing, or monitoring costs; or unpaid liens, any or all of which are owed to Miami-Dade County pursuant to the provisions of the Code of Miami-Dade County, Florida, a hold on the review may be placed on this application.</b></p>			

## Series RFI – 5.6 K-factor “Royal Flush II” Concealed Pendent Sprinklers Quick & Standard Response, Standard Coverage

### General Description

The TYCO Series RFI 5.6 K-factor, “Royal Flush II” Concealed Pendent Sprinklers Quick Response (3-mm bulb) and Standard Response (5-mm bulb), are decorative sprinklers featuring a flat cover plate designed to conceal the sprinkler. These sprinklers are optimal for architecturally sensitive areas such as hotel lobbies, office buildings, churches, and restaurants.

Each sprinkler includes a Cover Plate/Retainer Assembly and a Sprinkler/Support Cup Assembly. The separable, two-piece assembly design provides the following benefits:

- Allows installation of the sprinklers and pressure testing of the fire protection system prior to installation of a suspended ceiling or application of the finish coating to a fixed ceiling.
- Permits the removal of suspended ceiling panels for access to building service equipment without having to first shut down the fire protection system and remove sprinklers.
- Provides for 1/2 inch (12,7 mm) of vertical adjustment to allow a measure of flexibility in determining the length of fixed piping to cut for the sprinkler drops.

The Series RFI Sprinklers are shipped with a Disposable Protective Cap. The Protective Cap is temporarily removed during installation and replaced to help protect the sprinkler during ceiling in-

stallation or finish. The tip of the Protective Cap can be used to mark the center of the ceiling hole into plaster board or ceiling tiles by gently pushing the ceiling product against the Protective Cap. When ceiling installation is complete, the Protective Cap is removed and the Cover Plate/Retainer Assembly is installed.

As an option, the Series RFI Standard Response (5-mm bulb) “Royal Flush II” Concealed Pendent Sprinklers can be fitted with a silicone Air and Dust Seal. (Refer to Figure 5.) The Air and Dust Seal is intended for sensitive areas where it is desirable to prevent air and dust from the area above the ceiling to pass through the cover plate.

#### NOTICE

*The Series RFI Concealed Pendent Sprinklers described herein must be installed and maintained in compliance with this document and with the applicable standards of the National Fire Protection Association, in addition to the standards of any authorities having jurisdiction. Failure to do so may impair the performance of these devices.*

*The owner is responsible for maintaining their fire protection system and devices in proper operating condition. The installing contractor or sprinkler manufacturer should be contacted with any questions.*

### Sprinkler Identification Number (SIN)

TY3531 – 3 mm bulb  
TY3551 – 5 mm bulb

### Technical Data

#### Sprinkler Approvals

Approvals apply only to the service conditions indicated in the Design Criteria section.



- TY3531 (3-mm Bulb) is UL Listed, C-UL Listed, VdS Approved (Certificate No. G4090007), and NYC Approved (MEA 353-01-E) as Quick Response.
- TY3531 (3-mm Bulb) is FM and LPCB Approved (Ref. No. 094a/10) Approved as Standard Response. Factory Mutual and LPCB do not approve any concealed sprinklers for quick response.
- TY3551 (5-mm Bulb) is UL Listed, C-UL Listed, FM Approved, LPCB Approved (Ref. No. 094a/9), and NYC Approved (MEA 353-01-E) as Standard Response.

#### Approvals for Air and Dust Seal

UL and C-UL Listed for use with the RFI Standard Response Concealed Sprinkler (TY3551).

#### Maximum Working Pressure

Maximum 250 psi (17,3 bar) by UL, C-UL, and NYC

Maximum 175 psi (12,1 bar) by FM, VdS, and LPCB

#### Temperature Rating

155°F (68°C) Sprinkler with  
139°F (59°C) Plate

200°F (93°C) Sprinkler with  
165°F (74°C) Plate

#### Discharge Coefficient

K= 5.6 GPM/psi<sup>1/2</sup> (80,6 LPM/bar<sup>1/2</sup>)

#### Adjustment

1/2 inch (12,7 mm)

#### Finishes

See the Ordering Procedure section.

#### IMPORTANT

*Always refer to Technical Data Sheet TFP700 for the “INSTALLER WARNING” that provides cautions with respect to handling and installation of sprinkler systems and components. Improper handling and installation can permanently damage a sprinkler system or its components and cause the sprinkler to fail to operate in a fire situation or cause it to operate prematurely.*

**Physical Characteristics**

Frame .....	Bronze
Support Cup .....	Chrome Plated Steel
Guide Pins .....	Stainless Steel
Deflector .....	Bronze
Compression Screw .....	Brass
Bulb .....	Glass
Cap .....	Bronze or Copper
Sealing Assembly .....	Beryllium Nickel w/ TEFLON
Cover Plate .....	Brass
Retainer .....	Brass
Ejection Spring .....	Stainless Steel

**Design Criteria**

The TYCO Series RFII 5.6 K-factor, "Royal Flush II" Concealed Pendent Sprinklers are intended for fire protection systems designed in accordance with the standard installation rules recognized by the applicable Listing or Approval agency; for example, UL Listing is based on NFPA 13 and VdS Approval is based on the CEA 4001.

For more information on LPCB and VdS Approvals, contact Tyco Fire Protection Products at the following office:

Enschede, Netherlands  
 Telephone: 31-53-428-4444  
 Fax: 31-53-428-3377

The Series RFII Concealed Pendent Sprinklers are only listed and approved with the Series RFII Concealed Cover Plates having a factory applied finish.

**NOTICE**


Do not use the Series RFII in applications where the air pressure above the ceiling is greater than that below. Down drafts through the Sprinkler/Support Cup Assembly can delay sprinkler operation in a fire situation.

**Operation**

When exposed to heat from a fire, the Cover Plate, normally soldered to the Retainer at three points, falls away to expose the Sprinkler/Support Cup Assembly.

The Deflector — supported by the Guide Pins — then drops down to its operational position.

The glass bulb contains a fluid that expands when exposed to heat. When the rated temperature is reached, the fluid expands sufficiently to shatter the glass bulb, activating the sprinkler and allowing water to flow.



**Installation**

The TYCO Series RFII 5.6 K-factor, "Royal Flush II" Concealed Pendent Sprinklers must be installed in accordance with this section.



**General Instructions**

Do not install any bulb-type sprinkler if the bulb is cracked or there is a loss of liquid from the bulb. With the sprinkler held horizontally, a small air bubble should be present. The diameter of the air bubble is approximately 1/16 inch (1,6 mm) for the 155°F (68°C) and 3/32 inch (2,4 mm) for the 200°F (93°C) temperature ratings.

A leak-tight 1/2 inch NPT sprinkler joint should be obtained by applying a minimum to maximum torque of 7 to 14 ft.-lbs. (9,5 to 19,0 Nm). Higher levels of torque can distort the sprinkler Inlet with consequent leakage or impairment of the sprinkler.

Do not attempt to compensate for insufficient adjustment in the Sprinkler by under- or over-tightening the Sprinkler/Support Cup Assembly. Re-adjust the position of the sprinkler fitting to suit.

- Step 1.** Install the sprinkler only in the pendent position with the center-line of the sprinkler perpendicular to the mounting surface.
- Step 2.** Remove the Protective Cap.
- Step 3.** With pipe thread sealant applied to the pipe threads, hand-tighten the sprinkler into the sprinkler fitting.
- Step 4.** Wrench-tighten the sprinkler using only the RFII Sprinkler Wrench. (Refer to Figure 3.) Apply the RFII Sprinkler Wrench to the Sprinkler as shown in Figure 3.
- Step 5.** Replace the Protective Cap by pushing it upwards until it bottoms out against the Support Cup. (Refer to Figure 4.) The Protective Cap helps prevent damage to the Deflector and



Arms during ceiling installation and/or finish. You can also use the Protective Cap to locate the center of the clearance hole by gently pushing the ceiling material up against the center point of the Protective Cap.

**NOTICE**


As long as the Protective Cap remains in place, the system is considered "Out of Service".

**Step 6.** After the ceiling has been completed with the 2-1/2 inch (63,5 mm) diameter clearance hole and in preparation for installing the Cover Plate/Retainer Assembly, remove and discard the Protective Cap. Verify that the Deflector moves up and down freely.

If the Sprinkler is damaged and the Deflector does not move up and down freely, replace the entire Sprinkler. Do not attempt to modify or repair a damaged sprinkler.

**Step 7.** When installing an Air and Dust Seal, refer to Figure 5; otherwise, proceed to Step 8. To attach the Air and Dust Seal, verify the angle of the outside edge of the seal is oriented according to Figure 5. Start the edge of the Retainer in the grooved slot of the Air and Dust Seal and continue around the retainer until the entire Air and Dust Seal is engaged.

**Step 8.** Screw on the Cover Plate/Retainer Assembly until the Retainer (shown in Figure 2) or the Air and Dust Seal (shown in Figure 5) contacts the ceiling. Do not continue to screw on the Cover Plate/Retainer Assembly so that it lifts a ceiling panel out of its normal position. If you cannot engage the Cover Plate/Retainer Assembly with the Support Cup or you cannot engage the Cover Plate/Retainer Assembly sufficiently to contact the ceiling, you must reposition the Sprinkler Fitting.



## Care and Maintenance

The TYCO Series RFI 5.6 K-factor, "Royal Flush II" Concealed Pendent Sprinklers must be maintained and serviced in accordance with this section.

Before closing a fire protection system main control valve for maintenance work on the fire protection system that it controls, obtain permission to shut down the affected fire protection system from the proper authorities and notify all personnel who may be affected by this action.

Absence of the Cover Plate/Retainer Assembly can delay sprinkler operation in a fire situation.

When properly installed, there is a nominal 3/32 inch (2,4 mm) air gap between the lip of the Cover Plate and the ceiling, as shown in Figure 2.

This air gap is necessary for proper operation of the sprinkler. If the ceiling requires repainting after sprinkler installation, ensure that the new paint does not seal off any of the air gap.

Do not pull the Cover Plate relative to the Enclosure. Separation may result.

Sprinklers which are found to be leaking or exhibiting visible signs of corrosion must be replaced.

Automatic sprinklers must never be painted, plated, coated, or otherwise altered after leaving the factory. Modified sprinklers must be replaced. Sprinklers that have been exposed to corrosive products of combustion, but have not operated, should be replaced if they cannot be completely cleaned by wiping the sprinkler with a cloth or by brushing it with a soft bristle brush.

Care must be exercised to avoid damage to the sprinklers - before, during, and after installation. Sprinklers damaged by dropping, striking, wrench twist/slippage, or the like, must be replaced. Also, replace any sprinkler that has a cracked bulb or that has lost liquid from its bulb. (Ref. Installation Section.)

Exercise care to avoid damage to sprinklers before, during, and after installation. Replace sprinklers damaged by dropping, striking, wrench twisting, wrench slipping, or the like. Also, replace any sprinkler that has a cracked bulb or that has lost liquid from its bulb. (Refer to the Installation section.)




FIGURE 5  
OPTIONAL AIR AND DUST SEAL FOR SERIES RFI (TY3551)

If you must remove a sprinkler, do not reinstall it or a replacement without reinstalling the Cover Plate/Retainer Assembly. If a Cover Plate/Retainer Assembly becomes dislodged during service, replace it immediately.

The owner is responsible for the inspection, testing, and maintenance of their fire protection system and devices in compliance with this document, as well as with the applicable standards of the National Fire Protection Association (e.g., NFPA 25), in addition to the standards of any other authorities having jurisdiction. Contact the installing contractor or sprinkler manufacturer regarding any questions.

Automatic sprinkler systems should be inspected, tested, and maintained by a qualified Inspection Service in accordance with local requirements and/or national code.

## Ordering Procedure

Contact your local distributor for availability. When placing an order, indicate the full product name.

### Sprinkler/Support Cup Assembly

Specify: Series RFI (specify SIN), K=5.6, "Royal Flush II" Pendent Sprinklers (specify) temperature rating and (specify) finish, P/N (specify).

	155°F (68°C)	200°F (93°C)
TY3531	51-792-1-155	51-792-1-200
TY3551	51-790-1-155	51-790-1-200

### Separately Ordered Cover Plate/Retainer Assembly:

Specify: (temperature rating from below) Series RFI Concealed Cover Plate with (finish), P/N (specify).

	139°F (59°C)(a)	165°F (74°C)(b)
Grey White (RAL9002) . . . . .	56-792-0-135	56-792-0-165
Brass . . . . .	56-792-1-135	56-792-1-165
Pure White (c) (RAL9010) . . . . .	56-792-3-135	56-792-3-165
Signal White (RAL9003) . . . . .	56-792-4-135	56-792-4-165
Jet Black (RAL9005) . . . . .	56-792-6-135	59-792-6-165
Brushed Chrome . . . . .	56-792-8-135	56-792-8-165
Chrome . . . . .	56-792-9-135	56-792-9-165
Custom . . . . .	56-792-X-135	56-792-X-165

- (a) For use with 155°F (68°C) sprinklers.
- (b) For use with 200°F (93°C) sprinklers.
- (c) Eastern Hemisphere sales only.

### Sprinkler Wrench

Specify: RFI Sprinkler Wrench, P/N 56-000-1-075.

### Air and Dust Seal

Specify: Air and Dust Seal, P/N 56-908-1-001.



Address: <b>14201 NW 60 AVE 8C</b>
Folio #: <b>3220240110010</b>
MDC Process #: <b>M2026003985</b>
MDC Tracking #: <b>322600 3985</b>
Job Description: <b>FIRE SPRINKLER</b>

Master Permit #: **BLC2025-1226**

Sub Permit #: **SME2025-3195**

Revision #:

**OFFICE USE ONLY**

ZONING	<input type="checkbox"/> Approved	Date	Disapproved	BUILDING	<input type="checkbox"/> Approved	Date	Disapproved	STRUCT.	<input type="checkbox"/> Approved	Date	Disapproved
	Date				Date				Date		
	Initials				Initials				Initials		
ROOFING	<input type="checkbox"/> Approved	Date	Disapproved	ELECT.	<input type="checkbox"/> Approved	Date	Disapproved	MECH.	<input checked="" type="checkbox"/> Approved	Date	Disapproved
	Date				Date				Date		
	Initials				Initials				Initials		
PLUMBING	<input type="checkbox"/> Approved	Date	Disapproved	FLOOD	<input type="checkbox"/> Approved	Date	Disapproved		<input type="checkbox"/> Approved	Date	Disapproved
	Date				Date				Date		
	Initials				Initials				Initials		

**PLANS CHECKED-OUT**

DATE	NAME

**PLANS CHECKED-IN**

DATE	NAME

	AMOUNTS
BASE PERMIT	
ZONING FEE	
CODE COMPLIANCE FEE	
TECHNOLOGY FEE	
DBPR SURCH. STATE	
DBPR SURCH. BUILDING	
SCANNING FEE	
WORK W/O PERMIT FEE	
UPFRONT FEE PAID	
BALANCE DUE:	



6601 Main St • Miami Lakes, Florida, 33014  
 Office: (305) 827-4015 • Fax: (305) 558-9884  
 Website: www.miamilakes-fl.gov

# BUILDING PERMIT APPLICATION

Job Address: 14201 NW 60TH AVENUE

Unit #:

Folio #: 32- 2024-011-0010

Owner-Builder:

Master Permit #: BLC 2025-1226 Sub Permit #: SHE 2025-3195 Revision #: \_\_\_\_\_

OWNER INFORMATION	NAME : CORDIS US CORP	LEGAL USE/ WORK	Current Use of Property: WAREHOUSE
	Address: 14201 NW 60 AVE		Job Description <u>ADD/RELOCATE (48) FIRE SPRINKLER HEADS</u>
	City, State, Zip MIAMI LAKES, FL 33014		
	Phone #: _____ Cell #: _____		JOB COST \$ <u>13,750</u> AREA/LENGTH: _____ SF/LF
	Email Address: _____		Residential <input type="checkbox"/> Multi-Family <input type="checkbox"/> Commercial <input checked="" type="checkbox"/> Industrial <input type="checkbox"/>
CONTRACTOR INFORMATION	Company Name: <u>American Fire Sprinkler Services LLC</u>	ARCHITECT/ ENGINEER	Code in Effect: _____
	Qualifier Name: OMAR OWEIS		Occupancy: _____
	License # FPC17-000109		Construction Type: _____
	Address 3371 NW 154TH TERRACE		Flood Zone/B.F.E.: _____ F.F.E.: _____
	City, State, Zip MIAMI GARDENS, FL 33054		Firm Name: _____
	Phone #: 305-628-0100 Cell #: 305-525-2331		A/E of record: _____
Email Address: MIKE@AMERICANPERMITTING.COM	License # _____		
	Address _____		
	City, State, Zip _____		
	Phone #: _____ Cell #: _____		
	Email Address: _____		
Permit Type -- Check only One		Change to Permit -- Check only One	
<input checked="" type="checkbox"/> Building <input type="checkbox"/> Electrical <input type="checkbox"/> Mechanical <input type="checkbox"/> Plumbing/Gas <input type="checkbox"/> Paving/Drainage <input type="checkbox"/> Sign <input type="checkbox"/> Roofing <input type="checkbox"/> P/W		<input type="checkbox"/> Extension <input type="checkbox"/> Renewal <input type="checkbox"/> Revision <input type="checkbox"/> Change Contractor <input checked="" type="checkbox"/> Shop Drawing <input type="checkbox"/> Cancellation	

Application is hereby made to obtain a permit to do work and installation as indicated. I certify that no work or installation has commenced prior to the issuance of a permit and that all work will be performed to meet the standards, of all laws regulating construction in this jurisdiction. I understand that a separate permit must be secured for ELECTRICAL WORK, MECHANICAL, PLUMBING, SIGNS, WELLS, POOLS, RE-ROOFING, SHUTTERS, WINDOWS, FURNACES, BOILERS, HEATERS, TANKS, and AIR CONDITIONERS, etc. I understand that in signing this application I am responsible for the supervision and completion of the construction including scheduling of inspections and obtaining final inspections in accordance with the plans and specification WARNING TO OWNER: YOUR FAILURE TO RECORD A NOTICE OF COMMENCEMENT MAY RESULT IN YOU PAYING TWICE FOR IMPROVEMENTS TO YOUR PROPERTY. IF YOU INTEND TO OBTAIN FINANCING, CONSULT WITH YOUR ATTORNEY OR LENDER BEFORE RECORDING YOUR NOTICE OF COMMENCEMENT. OWNER/CONTRACTOR AFFIDAVIT: I Certify that all the foregoing information is accurate and that all work will be done in compliance with all applicable laws regulating construction and zoning.

X  
 Signature of Owner or Owner's Agent \_\_\_\_\_ Date \_\_\_\_\_


X  
 Signature of Qualifier \_\_\_\_\_ Date 05/07/2025

Print Name of Owner or Owner's Agent \_\_\_\_\_

Print Name of Qualifier OMAR OWEIS

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_  
 Sworn to and subscribed before me this \_\_\_\_\_ 20\_\_\_\_  
 by \_\_\_\_\_ (SEAL)  
 Personally known  or I.D. \_\_\_\_\_

STATE OF FLORIDA COUNTY OF MIAMI DADE  
 Sworn to and subscribed before me this MAY 7TH 20, 25  
 by OMAR OWEIS \_\_\_\_\_ (SEAL)  
 Personally known  or I.D. \_\_\_\_\_



**NOTICE:** In addition to the requirements of this permit, there may be additional deed restrictions enforced by the home owner's association that may be applicable to this property that may be found in the public records of this county, and there may be additional permits required from other governmental entities such as water management districts, state agencies, or federal agencies.